

**Vermont Yankee Nuclear Power Station  
SAFSTOR Alternative Decommissioning Cost Estimate  
(thousands of 2014 dollars)**

Activity Index	Costs run: Fri, Aug 22, 2014 at 09:27:05 DECER Version 2010.09.091 Activity Description	Decon Cost	Removal Cost	Packaging Costs	Transport Costs	LLRW Disposal Costs	Other Costs	Total Contingency	Total Costs	NRC Lic. Term. Costs	Spent Fuel Management Costs	Site Restoration Costs	Burial Volumes				Burial / Processed Wt., Lbs.	Craft Manhours	Utility and Contractor Manhours
													Class A Cu. Feet	Class B Cu. Feet	Class C Cu. Feet	GTCC Cu. Feet			
<b>PERIOD 0 - Pre-Shutdown Early Planning</b>																			
<b>Period start date: Wednesday, January 1, 2014</b>																			
<b>Period end date: Thursday, January 1, 2015</b>																			
<b>Period duration: 11.99 months</b>																			
<b>Period 0 Additional Costs</b>																			
0.2.1	Financing Cost and Interest	-	-	-	-	-	520	-	520	520	-	-	-	-	-	-	-		
0.2.2	ARO - Outside Contractor Support Studies / Submittals (LT-CTC)	-	-	-	-	-	2,063	-	2,063	2,063	-	-	-	-	-	-	-		
0.2.3	ARO - Outside Contractor Support Decommissioning Cost Estimates (LT-DCE)	-	-	-	-	-	1,500	-	1,500	1,500	-	-	-	-	-	-	-		
0.2.4	ARO - Miscellaneous Expenses (LT-Misc)	-	-	-	-	-	1,011	-	1,011	1,011	-	-	-	-	-	-	-		
0.2.5	ARO - Outside Contractor Support Plant Modifications (LT-Mod's)	-	-	-	-	-	1,567	-	1,567	1,567	-	-	-	-	-	-	-		
0.2.6	ARO - ISFSI Pad (SF-ISFSI)	-	-	-	-	-	3,927	723	4,650	-	4,650	-	-	-	-	-	-		
0.2.7	ARO - Miscellaneous Expenses (SF-MISC)	-	-	-	-	-	95	-	95	-	95	-	-	-	-	-	-		
0.2.8	ARO - DPO and PMO Payroll (LT-PAYROLL)	-	-	-	-	-	3,976	-	3,976	3,976	-	-	-	-	-	-	-		
0.2.9	ARO - Outside Consultants (LT-Consult)	-	-	-	-	-	1,000	-	1,000	1,000	-	-	-	-	-	-	-		
0.2.10	ARO - (Other)	-	-	-	-	-	598	-	598	598	-	-	-	-	-	-	-		
0.2.11	ARO - Spent Fuel Cask (SF-CASK)	-	-	-	-	-	8	-	8	-	8	-	-	-	-	-	-		
0.2.29	Third Party Advisor	-	-	-	-	-	630	-	630	630	-	-	-	-	-	-	-		
0.2.35	Non-Incremental Labor / Site Staff Support (Non-DPO) Planning and Preparation	-	-	-	-	-	1,786	14	1,800	1,800	-	-	-	-	-	-	-		
0.2	Subtotal Period 0 Additional Costs	-	-	-	-	-	18,681	737	19,418	14,665	4,753	-	-	-	-	-	-		
<b>Period 0 Period-Dependent Costs</b>																			
0.4.4	NRC Fees	-	-	-	-	-	455	45	500	500	-	-	-	-	-	-	-		
0.4	Subtotal Period 0 Period-Dependent Costs	-	-	-	-	-	455	45	500	500	-	-	-	-	-	-	-		
<b>PERIOD 0 TOTALS</b>																			
<b>Period start date: Thursday, January 1, 2015</b>																			
<b>Period end date: Sunday, March 1, 2015</b>																			
<b>Period duration: 1.94 months</b>																			
<b>Period 1a Direct Decommissioning Activities</b>																			
<b>Period 1a Additional Costs</b>																			
1a.2.1	Financing Cost and Interest	-	-	-	-	-	116	-	116	116	-	-	-	-	-	-	-		
1a.2.2	ISFSI Pad	-	-	-	-	-	809	408	1,217	-	1,217	-	-	-	-	-	-		
1a.2.3	ISFSI Pad (Utility Staff Contribution)	-	-	-	-	-	(201)	-	(201)	-	(201)	-	-	-	-	-	-		
1a.2.8	Security Phase 1 & II (Lic Term)	-	-	-	-	-	180	11	191	191	-	-	-	-	-	-	-		
1a.2.9	Security Phase 1 & II (Lic Term) (Utility Staff Contribution)	-	-	-	-	-	(15)	-	(15)	(15)	-	-	-	-	-	-	-		
1a.2.10	Security Phase 1 & II (Spent Fuel)	-	-	-	-	-	358	-	358	-	358	-	-	-	-	-	-		
1a.2.11	Security Phase 1 & II (Spent Fuel) (Utility Staff Contribution)	-	-	-	-	-	(14)	-	(14)	(14)	-	-	-	-	-	-	-		
1a.2.12	Rad Waste / Water Mgt.	-	-	-	-	-	143	54	198	198	-	-	-	-	-	-	-		
1a.2.13	Rad Waste / Water Mgt. (Utility Staff Contribution)	-	-	-	-	-	(6)	-	(6)	(6)	-	-	-	-	-	-	-		
1a.2.14	B.5.B	-	-	-	-	-	40	-	40	40	-	-	-	-	-	-	-		
1a.2.16	System Abandonment	-	-	-	-	-	50	-	50	50	-	-	-	-	-	-	-		
1a.2.17	System Abandonment (Utility Staff Contribution)	-	-	-	-	-	(22)	-	(22)	(22)	-	-	-	-	-	-	-		
1a.2.18	Building Layups	-	-	-	-	-	249	58	307	307	-	-	-	-	-	-	-		
1a.2.19	Building Layups (Utility Staff Contribution)	-	-	-	-	-	(20)	-	(20)	(20)	-	-	-	-	-	-	-		
1a.2.20	Credit (Site Non-Labor Overhead, Insurance, NRC Fees, Property Taxes, EP Fees, Energy, Corporate A&G while defueling)	-	-	-	-	-	(2,401)	-	(2,401)	(2,401)	-	-	-	-	-	-	-		
1a.2.21	Credit (Utility and Security Staff Labor - O&M Expenditures while defueling)	-	-	-	-	-	(3,294)	-	(3,294)	(3,294)	-	-	-	-	-	-	(49,727)		
1a.2.22	State of Vermont Payment in Lieu of Taxes	-	-	-	-	-	808	-	808	808	-	-	-	-	-	-	-		
1a.2.23	E Plan and Licensing Contractors	-	-	-	-	-	36	-	36	36	-	-	-	-	-	-	-		
1a.2.27	Asbestos Shipments	-	-	-	-	-	7	-	7	7	-	-	-	-	-	-	-		
1a.2.28	ARO - (Other)	-	-	-	-	-	48	-	48	48	-	-	-	-	-	-	-		
1a.2.29	Third Party Advisor	-	-	-	-	-	99	-	99	99	-	-	-	-	-	-	-		
1a.2.30	IT Support and IT Projects	-	-	-	-	-	78	-	78	78	-	-	-	-	-	-	-		
1a.2.33	Fees Paid by Headquarters (excl NEI annual)	-	-	-	-	-	14	-	14	-	14	-	-	-	-	-	-		
1a.2.36	Communication Plan	-	-	-	-	-	48	-	48	48	-	-	-	-	-	-	-		
1a.2.37	Transcanada - Min River Flow Contract	-	-	-	-	-	4	-	4	4	-	-	-	-	-	-	-		
1a.2.38	NEI Annual Fee	-	-	-	-	-	10	-	10	-	10	-	-	-	-	-	-		
1a.2.39	PMO Discretionary Contingency	-	-	-	-	-	-	404	404	404	-	-	-	-	-	-	-		
1a.2	Subtotal Period 1a Additional Costs	-	-	-	-	-	(2,875)	935	(1,940)	(3,337)	1,398	-	-	-	-	-	(49,727)		
<b>Period 1a Collateral Costs</b>																			
1a.3.1	Legal (License Termination)	-	-	-	-	-	326	-	326	326	-	-	-	-	-	-	-		
1a.3.2	PMO Labor Support (excluding Legal)	-	-	-	-	-	389	58	448	448	-	-	-	-	-	-	-		
1a.3	Subtotal Period 1a Collateral Costs	-	-	-	-	-	715	58	774	774	-	-	-	-	-	-	-		
<b>Period 1a Period-Dependent Costs</b>																			
1a.4.1	Insurance	-	-	-	-	-	313	31	345	345	-	-	-	-	-	-	-		
1a.4.2	Property taxes	-	-	-	-	-	118	12	129	129	-	-	-	-	-	-	-		
1a.4.3	Health physics supplies	-	67	-	-	-	-	17	84	84	-	-	-	-	-	-	-		
1a.4.4	Disposal of DAW generated	-	-	2	2	5	-	2	10	10	-	99	-	-	-	1,970	3		
1a.4.5	Plant energy budget	-	-	-	-	-	598	90	688	688	-	-	-	-	-	-	-		
1a.4.6	NRC Fees	-	-	-	-	-	299	30	329	329	-	-	-	-	-	-	-		
1a.4.7	Emergency Planning Fees	-	-	-	-	-	837	84	920	-	920	-	-	-	-	-	-		
1a.4.8	Site Non-Labor Overhead	-	-	-	-	-	681	102	783	783	-	-	-	-	-	-	-		
1a.4.9	Corporate A&G Cost	-	-	-	-	-	1,398	210	1,608	1,608	-	-	-	-	-	-	-		
1a.4.10	Security Staff Cost	-	-	-	-	-	1,838	276	2,114	2,114	-	-	-	-	-	-	45,514		
1a.4.11	Utility Staff Cost	-	-	-	-	-	4,547	682	5,230	5,230	-	-	-	-	-	-	68,440		
1a.4	Subtotal Period 1a Period-Dependent Costs	-	67	2	2	5	10,630	1,535	12,241	11,320	920	-	99	-	-	1,970	3		
<b>1a.0</b>	<b>TOTAL PERIOD 1a COST</b>	-	67	2	2	5	8,471	2,528	11,075	8,757	2,318	-	99	-	-	1,970	3		



**Vermont Yankee Nuclear Power Station  
SAFSTOR Alternative Decommissioning Cost Estimate  
(thousands of 2014 dollars)**

Activity Index	Activity Description	Costs run: Fri, Aug 22, 2014 at 09:27:05 DECER Version 2010.09.091											Burial Volumes				Burial / Processed Wt., Lbs.	Craft Manhours	Utility and Contractor Manhours
		Decon Cost	Removal Cost	Packaging Costs	Transport Costs	LLRW Disposal Costs	Other Costs	Total Contingency	Total Costs	NRC Lic. Term. Costs	Spent Fuel Management Costs	Site Restoration Costs	Class A Cu. Feet	Class B Cu. Feet	Class C Cu. Feet	GTCC Cu. Feet			
Period 2a Additional Costs (continued)																			
2a.2.31	SAFSTOR Organization Severance	-	-	-	-	-	3,707	-	3,707	3,707	-	-	-	-	-	-	-	-	-
2a.2.33	Fees Paid by Headquarters (excl NEI annual)	-	-	-	-	-	359	-	359	-	359	-	-	-	-	-	-	-	-
2a.2.36	Communication Plan	-	-	-	-	-	170	-	170	170	-	-	-	-	-	-	-	-	-
2a.2.37	Transcanada - Min River Flow Contract	-	-	-	-	-	104	-	104	104	-	-	-	-	-	-	-	-	-
2a.2.38	NEI Annual Fee	-	-	-	-	-	250	-	250	-	250	-	-	-	-	-	-	-	-
2a.2.39	PMO Discretionary Contingency	-	-	-	-	-	-	6,383	6,383	6,383	-	-	-	-	-	-	-	-	-
2a.2	Subtotal Period 2a Additional Costs	-	-	-	-	-	117,564	20,955	138,519	14,918	123,601	-	-	-	-	-	-	-	-
<b>Period 2a Collateral Costs</b>																			
2a.3.1	Legal (License Termination)	-	-	-	-	-	6,752	-	6,752	6,752	-	-	-	-	-	-	-	-	-
2a.3.2	PMO Labor Support (excluding Legal)	-	-	-	-	-	5,262	789	6,052	6,052	-	-	-	-	-	-	-	-	-
2a.3	Subtotal Period 2a Collateral Costs	-	-	-	-	-	12,014	789	12,804	12,804	-	-	-	-	-	-	-	-	-
<b>Period 2a Period-Dependent Costs</b>																			
2a.4.1	Insurance	-	-	-	-	-	3,072	307	3,379	2,239	1,140	-	-	-	-	-	-	-	-
2a.4.2	Property taxes	-	-	-	-	-	216	22	238	238	-	-	-	-	-	-	-	-	-
2a.4.3	Health physics supplies	-	700	-	-	-	-	175	875	875	-	-	-	-	-	-	-	-	-
2a.4.4	Disposal of DAW generated	-	-	17	17	48	-	16	99	99	-	962	-	-	-	-	19,238	31	-
2a.4.5	Plant energy budget	-	-	-	-	-	8,764	1,315	10,079	779	9,300	-	-	-	-	-	-	-	-
2a.4.6	NRC Fees	-	-	-	-	-	3,523	352	3,875	3,875	-	-	-	-	-	-	-	-	-
2a.4.7	Emergency Planning Fees	-	-	-	-	-	5,930	593	6,523	-	6,523	-	-	-	-	-	-	-	-
2a.4.8	Site Non-Labor Overhead	-	-	-	-	-	8,520	1,278	9,798	374	9,424	-	-	-	-	-	-	-	-
2a.4.9	Corporate A&G Cost	-	-	-	-	-	9,851	1,478	11,329	563	10,766	-	-	-	-	-	-	-	-
2a.4.10	Security Staff Cost	-	-	-	-	-	32,747	4,912	37,659	3,092	34,568	-	-	-	-	-	-	-	756,651
2a.4.11	Utility Staff Cost	-	-	-	-	-	23,434	3,515	26,949	5,027	21,923	-	-	-	-	-	-	-	347,886
2a.4	Subtotal Period 2a Period-Dependent Costs	-	700	17	17	48	96,059	13,963	110,804	17,161	93,643	-	962	-	-	-	19,238	31	1,104,537
<b>2a.0</b>	<b>TOTAL PERIOD 2a COST</b>	-	700	17	17	48	226,338	35,870	262,990	45,746	217,244	-	962	-	-	-	19,238	31	1,104,537
<b>PERIOD 2aa - Post Spent Fuel Pool Layup Activities</b>																			
Period start date: July 1, 2020																			
Period end date: Friday, January 1, 2021																			
Period duration: 6.05 months																			
<b>Period 2aa Direct Decommissioning Activities</b>																			
2aa.1.1	Prepare support equipment for storage	-	485	-	-	-	-	73	558	558	-	-	-	-	-	-	-	3,000	-
2aa.1.2	Install containment pressure equal. lines	-	48	-	-	-	-	7	55	55	-	-	-	-	-	-	-	700	-
2aa.1.3	Interim survey prior to dormancy	-	-	-	-	-	733	220	953	953	-	-	-	-	-	-	-	11,126	-
2aa.1.4	Secure building accesses	-	-	-	-	-	-	-	a	-	-	-	-	-	-	-	-	-	-
2aa.1.5	Prepare & submit interim report	-	-	-	-	-	74	11	85	85	-	-	-	-	-	-	-	-	583
2aa.1	Subtotal Period 2aa Activity Costs	-	533	-	-	-	807	311	1,651	1,651	-	-	-	-	-	-	-	14,826	583
<b>Period 2aa Additional Costs</b>																			
2aa.2.1	Financing Cost and Interest	-	-	-	-	-	261	-	261	261	-	-	-	-	-	-	-	-	-
2aa.2.25	Reactivate Rail Spur (\$125 K)	-	-	-	-	-	125	-	125	125	-	-	-	-	-	-	-	-	-
2aa.2.26	Spent Fuel Racks	658	77	130	256	798	-	599	2,517	2,517	-	10,634	-	-	-	-	638,066	1,332	-
2aa.2.31	SAFSTOR Organization Severance	-	-	-	-	-	905	-	905	905	-	-	-	-	-	-	-	-	-
2aa.2.33	Fees Paid by Headquarters (excl NEI annual)	-	-	-	-	-	43	-	43	-	43	-	-	-	-	-	-	-	-
2aa.2.37	Transcanada - Min River Flow Contract	-	-	-	-	-	13	-	13	13	-	-	-	-	-	-	-	-	-
2aa.2.38	NEI Annual Fee	-	-	-	-	-	30	-	30	-	30	-	-	-	-	-	-	-	-
2aa.2.39	PMO Discretionary Contingency	-	-	-	-	-	-	126	126	126	-	-	-	-	-	-	-	-	-
2aa.2	Subtotal Period 2aa Additional Costs	658	77	130	256	798	1,377	725	4,020	3,947	73	10,634	-	-	-	-	638,066	1,332	-
<b>Period 2aa Collateral Costs</b>																			
2aa.3.1	Process decommissioning water waste	58	-	32	138	147	-	89	464	464	-	367	-	-	-	-	22,008	72	-
2aa.3.3	Small tool allowance	-	13	-	-	-	-	2	15	15	-	-	-	-	-	-	-	-	-
2aa.3.4	Legal (License Termination)	-	-	-	-	-	804	-	804	804	-	-	-	-	-	-	-	-	-
2aa.3.5	PMO Labor Support (excluding Legal)	-	-	-	-	-	578	87	665	665	-	-	-	-	-	-	-	-	-
2aa.3	Subtotal Period 2aa Collateral Costs	58	13	32	138	147	1,382	178	1,949	1,949	-	367	-	-	-	-	22,008	72	-
<b>Period 2aa Period-Dependent Costs</b>																			
2aa.4.1	Insurance	-	-	-	-	-	266	27	292	292	-	-	-	-	-	-	-	-	-
2aa.4.2	Property taxes	-	-	-	-	-	3	0	4	4	-	-	-	-	-	-	-	-	-
2aa.4.3	Health physics supplies	-	210	-	-	-	-	53	263	263	-	-	-	-	-	-	-	-	-
2aa.4.4	Disposal of DAW generated	-	-	3	3	10	-	3	20	20	-	194	-	-	-	-	3,874	6	-
2aa.4.5	Plant energy budget	-	-	-	-	-	1,040	156	1,196	1,196	-	-	-	-	-	-	-	-	-
2aa.4.6	NRC Fees	-	-	-	-	-	287	29	316	316	-	-	-	-	-	-	-	-	-
2aa.4.7	Site Non-Labor Overhead	-	-	-	-	-	163	24	188	188	-	-	-	-	-	-	-	-	-
2aa.4.8	Corporate A&G Cost	-	-	-	-	-	598	90	687	687	-	-	-	-	-	-	-	-	-
2aa.4.9	Security Staff Cost	-	-	-	-	-	1,268	190	1,458	1,458	-	-	-	-	-	-	-	-	27,337
2aa.4.10	Utility Staff Cost	-	-	-	-	-	955	143	1,098	1,098	-	-	-	-	-	-	-	-	16,823
2aa.4	Subtotal Period 2aa Period-Dependent Costs	-	210	3	3	10	4,581	715	5,523	5,523	-	194	-	-	-	-	3,874	6	44,160
<b>2aa.0</b>	<b>TOTAL PERIOD 2aa COST</b>	716	834	165	397	954	8,147	1,929	13,143	13,070	73	11,195	-	-	-	-	663,948	16,236	44,743

**Vermont Yankee Nuclear Power Station  
SAFSTOR Alternative Decommissioning Cost Estimate  
(thousands of 2014 dollars)**

Activity Index	Activity Description	Decon Cost	Removal Cost	Packaging Costs	Transport Costs	LLRW Disposal Costs	Other Costs	Total Contingency	Total Costs	NRC Lic. Term. Costs	Spent Fuel Management Costs	Site Restoration Costs	Burial Volumes				Burial / Processed Wt., Lbs.	Craft Manhours	Utility and Contractor Manhours
													Class A Cu. Feet	Class B Cu. Feet	Class C Cu. Feet	GTCC Cu. Feet			
<b>PERIOD 2b - SAFSTOR Dormancy with Dry Spent Fuel Storage</b>																			
Period start date: Friday, January 1, 2021																			
Period end date: Wednesday, January 1, 2053																			
Period duration: 384 months																			
<b>Period 2b Direct Decommissioning Activities</b>																			
2b.1.1	Quarterly Inspection	-	-	-	-	-	-	-	a	-	-	-	-	-	-	-	-	-	-
2b.1.2	Semi-annual environmental survey	-	-	-	-	-	-	-	a	-	-	-	-	-	-	-	-	-	-
2b.1.3	Prepare reports	-	-	-	-	-	-	-	a	-	-	-	-	-	-	-	-	-	-
2b.1.4	Bituminous roof replacement	-	-	-	-	-	931	140	1,071	1,071	-	-	-	-	-	-	-	-	-
2b.1.5	Maintenance supplies	-	-	-	-	-	4,448	1,112	5,560	5,560	-	-	-	-	-	-	-	-	-
2b.1	Subtotal Period 2b Activity Costs	-	-	-	-	-	5,379	1,252	6,631	6,631	-	-	-	-	-	-	-	-	-
<b>Period 2b Additional Costs</b>																			
2b.2.1	Financing Cost and Interest	-	-	-	-	-	4,710	-	4,710	4,710	-	-	-	-	-	-	-	-	-
2b.2.2	NEI Annual Fee	-	-	-	-	-	1,920	-	1,920	-	1,920	-	-	-	-	-	-	-	-
2b.2	Subtotal Period 2b Additional Costs	-	-	-	-	-	6,630	-	6,630	4,710	1,920	-	-	-	-	-	-	-	-
<b>Period 2b Collateral Costs</b>																			
2b.3.1	Spent Fuel Capital and Transfer	-	-	-	-	-	12,540	1,881	14,421	-	14,421	-	-	-	-	-	-	-	-
2b.3.2	Legal (License Termination)	-	-	-	-	-	4,800	-	4,800	4,800	-	-	-	-	-	-	-	-	-
2b.3	Subtotal Period 2b Collateral Costs	-	-	-	-	-	17,340	1,881	19,221	4,800	14,421	-	-	-	-	-	-	-	-
<b>Period 2b Period-Dependent Costs</b>																			
2b.4.1	Insurance	-	-	-	-	-	15,633	1,563	17,196	17,196	-	-	-	-	-	-	-	-	-
2b.4.2	Property taxes	-	-	-	-	-	218	22	239	239	-	-	-	-	-	-	-	-	-
2b.4.3	Health physics supplies	-	2,601	-	-	-	-	650	3,252	3,252	-	-	-	-	-	-	-	-	-
2b.4.4	Disposal of DAW generated	-	-	63	63	177	-	60	363	363	-	-	3,539	-	-	-	70,783	115	-
2b.4.5	Plant energy budget	-	-	-	-	-	7,412	1,112	8,524	5,981	2,543	-	-	-	-	-	-	-	-
2b.4.6	NRC Fees	-	-	-	-	-	10,403	1,040	11,443	11,443	-	-	-	-	-	-	-	-	-
2b.4.7	Site Non-Labor Overhead	-	-	-	-	-	9,278	1,392	10,669	2,876	7,794	-	-	-	-	-	-	-	-
2b.4.8	Corporate A&G Cost	-	-	-	-	-	4,817	722	5,539	4,324	1,215	-	-	-	-	-	-	-	-
2b.4.9	Security Staff Cost	-	-	-	-	-	80,556	12,083	92,640	23,742	68,898	-	-	-	-	-	-	-	1,736,503
2b.4.10	Utility Staff Cost	-	-	-	-	-	60,672	9,101	69,773	38,603	31,170	-	-	-	-	-	-	-	1,068,617
2b.4	Subtotal Period 2b Period-Dependent Costs	-	2,601	63	63	177	188,988	27,746	219,638	108,018	111,620	-	3,539	-	-	-	70,783	115	2,805,120
2b.0	<b>TOTAL PERIOD 2b COST</b>	-	2,601	63	63	177	218,337	30,879	252,120	124,159	127,961	-	3,539	-	-	-	70,783	115	2,805,120
<b>PERIOD 2c - SAFSTOR Dormancy without Spent Fuel Storage</b>																			
Period start date: Wednesday, January 1, 2053																			
Period end date: Sunday, January 1, 2068																			
Period duration: 179.98 months																			
<b>Period 2c Direct Decommissioning Activities</b>																			
2c.1.1	Quarterly Inspection	-	-	-	-	-	-	-	a	-	-	-	-	-	-	-	-	-	-
2c.1.2	Semi-annual environmental survey	-	-	-	-	-	-	-	a	-	-	-	-	-	-	-	-	-	-
2c.1.3	Prepare reports	-	-	-	-	-	-	-	a	-	-	-	-	-	-	-	-	-	-
2c.1.4	Bituminous roof replacement	-	-	-	-	-	436	65	502	502	-	-	-	-	-	-	-	-	-
2c.1.5	Maintenance supplies	-	-	-	-	-	2,085	521	2,606	2,606	-	-	-	-	-	-	-	-	-
2c.1	Subtotal Period 2c Activity Costs	-	-	-	-	-	2,521	587	3,108	3,108	-	-	-	-	-	-	-	-	-
<b>Period 2c Additional Costs</b>																			
2c.2.1	Financing Cost and Interest	-	-	-	-	-	2,200	-	2,200	2,200	-	-	-	-	-	-	-	-	-
2c.2	Subtotal Period 2c Additional Costs	-	-	-	-	-	2,200	-	2,200	2,200	-	-	-	-	-	-	-	-	-
<b>Period 2c Period-Dependent Costs</b>																			
2c.4.1	Insurance	-	-	-	-	-	7,327	733	8,060	8,060	-	-	-	-	-	-	-	-	-
2c.4.2	Property taxes	-	-	-	-	-	102	10	112	112	-	-	-	-	-	-	-	-	-
2c.4.3	Health physics supplies	-	1,149	-	-	-	-	287	1,437	1,437	-	-	-	-	-	-	-	-	-
2c.4.4	Disposal of DAW generated	-	-	27	27	77	-	26	157	157	-	-	1,532	-	-	-	30,644	50	-
2c.4.5	Plant energy budget	-	-	-	-	-	2,437	366	2,803	2,803	-	-	-	-	-	-	-	-	-
2c.4.6	NRC Fees	-	-	-	-	-	3,223	322	3,545	3,545	-	-	-	-	-	-	-	-	-
2c.4.7	Site Non-Labor Overhead	-	-	-	-	-	1,172	176	1,348	1,348	-	-	-	-	-	-	-	-	-
2c.4.8	Corporate A&G Cost	-	-	-	-	-	1,762	264	2,026	2,026	-	-	-	-	-	-	-	-	-
2c.4.9	Security Staff Cost	-	-	-	-	-	9,676	1,451	11,127	11,127	-	-	-	-	-	-	-	-	281,726
2c.4.10	Utility Staff Cost	-	-	-	-	-	15,733	2,360	18,093	18,093	-	-	-	-	-	-	-	-	281,726
2c.4	Subtotal Period 2c Period-Dependent Costs	-	1,149	27	27	77	41,432	5,996	48,708	48,708	-	-	1,532	-	-	-	30,644	50	563,451
2c.0	<b>TOTAL PERIOD 2c COST</b>	-	1,149	27	27	77	46,153	6,582	54,016	54,016	-	-	1,532	-	-	-	30,644	50	563,451
<b>PERIOD 2 TOTALS</b>		716	5,284	274	504	1,256	498,975	75,260	582,269	236,990	345,279	-	17,228	-	-	-	784,613	16,433	4,517,852







Vermont Yankee Nuclear Power Station  
SAFSTOR Alternative Decommissioning Cost Estimate  
(thousands of 2014 dollars)

Table with columns: Activity Index, Activity Description, Decon Cost, Removal Cost, Packaging Costs, Transport Costs, LLRW Disposal Costs, Other Costs, Total Contingency, Total Costs, NRC Lic. Term. Costs, Spent Fuel Management Costs, Site Restoration Costs, Burial Volumes (Class A, B, C, GTCC), Burial / Processed Wt., Craft Manhours, Utility and Contractor Manhours. Includes sub-sections for Reactor Building, Turbine Building, and Augmented Offgas Building System Components.









**Vermont Yankee Nuclear Power Station  
SAFSTOR Alternative Decommissioning Cost Estimate  
(thousands of 2014 dollars)**

Activity Index	Activity Description	Decon Cost	Removal Cost	Packaging Costs	Transport Costs	LLRW Disposal Costs	Other Costs	Total Contingency	Total Costs	NRC Lic. Term. Costs	Spent Fuel Management Costs	Site Restoration Costs	Burial Volumes				Burial / Processed Wt., Lbs.	Craft Manhours	Utility and Contractor Manhours
													Class A Cu. Feet	Class B Cu. Feet	Class C Cu. Feet	GTCC Cu. Feet			
Demolition of Remaining Site Buildings (continued)																			
5b.1.1.21	Station Blackout Diesel	-	55	-	-	-	-	8	63	-	-	63	-	-	-	-	-	681	-
5b.1.1.22	Turbine	-	2,497	-	-	-	-	375	2,872	-	-	2,872	-	-	-	-	-	28,234	-
5b.1.1.23	Turbine Pedestal	-	656	-	-	-	-	98	754	-	-	754	-	-	-	-	-	6,331	-
5b.1.1.24	Turbine Storage Facility	-	127	-	-	-	-	19	147	-	-	147	-	-	-	-	-	1,986	-
5b.1.1.25	Vent Stack	-	760	-	-	-	-	114	874	-	-	874	-	-	-	-	-	9,329	-
5b.1.1.26	Vent Stack (Concrete Duct)	-	159	-	-	-	-	24	182	-	-	182	-	-	-	-	-	2,023	-
5b.1.1.27	Reactor (SFP & Sacrificial Shield)	-	32	-	-	-	-	5	37	-	-	37	-	-	-	-	-	512	-
5b.1.1	Totals	-	16,348	-	-	-	-	2,452	18,800	-	-	18,800	-	-	-	-	-	185,978	-
<b>Site Closeout Activities</b>																			
5b.1.2	Grade & landscape site	-	92	-	-	-	-	14	106	-	-	106	-	-	-	-	-	286	-
5b.1.3	Final report to NRC	-	-	-	-	-	198	30	227	227	-	-	-	-	-	-	-	-	1,560
5b.1	Subtotal Period 5b Activity Costs	-	92	-	-	-	198	43	333	227	-	106	-	-	-	-	-	286	1,560
<b>Period 5b Additional Costs</b>																			
5b.2.1	Financing Cost and Interest	-	-	-	-	-	1,240	-	1,240	-	-	1,240	-	-	-	-	-	-	-
5b.2.2	Intake & discharge structure cofferdams	-	665	-	-	-	-	100	764	-	-	764	-	-	-	-	-	6,383	-
5b.2.3	Concrete processing for concrete recycling	-	550	-	-	-	1,079	244	1,874	-	-	1,874	-	-	-	-	-	2,875	-
5b.2.4	Backfill underground services excavation	-	768	-	-	-	-	115	884	-	-	884	-	-	-	-	-	4,967	-
5b.2.5	Backfill structures	-	663	-	-	-	-	99	762	-	-	762	-	-	-	-	-	1,364	-
5b.2.6	Demolition and site restoration - ISFSI	-	1,066	-	-	-	120	178	1,364	-	-	1,364	-	-	-	-	-	11,667	160
5b.2.7	Disposal of construction debris from demolition	-	-	-	-	-	860	129	989	-	-	989	-	-	-	-	-	-	-
5b.2	Subtotal Period 5b Additional Costs	-	3,712	-	-	-	3,300	866	7,877	-	-	7,877	-	-	-	-	-	27,255	160
<b>Period 5b Collateral Costs</b>																			
5b.3.1	Small tool allowance	-	191	-	-	-	-	29	219	-	-	219	-	-	-	-	-	-	-
5b.3.2	Corporate A&G Cost	-	-	-	-	-	364	55	418	-	-	418	-	-	-	-	-	-	-
5b.3	Subtotal Period 5b Collateral Costs	-	191	-	-	-	364	83	637	-	-	637	-	-	-	-	-	-	-
<b>Period 5b Period-Dependent Costs</b>																			
5b.4.1	Insurance	-	-	-	-	-	64	6	70	-	-	70	-	-	-	-	-	-	-
5b.4.2	Property taxes	-	-	-	-	-	10	1	11	-	-	11	-	-	-	-	-	-	-
5b.4.3	Heavy equipment rental	-	4,970	-	-	-	-	746	5,716	-	-	5,716	-	-	-	-	-	-	-
5b.4.4	Plant energy budget	-	-	-	-	-	244	37	280	-	-	280	-	-	-	-	-	-	-
5b.4.5	NRC Fees	-	-	-	-	-	541	54	595	595	-	-	-	-	-	-	-	-	-
5b.4.6	Site Non-Labor Overhead	-	-	-	-	-	292	44	336	-	-	336	-	-	-	-	-	-	-
5b.4.7	Security Staff Cost	-	-	-	-	-	1,190	178	1,368	-	-	1,368	-	-	-	-	-	-	37,577
5b.4.8	DOC Staff Cost	-	-	-	-	-	10,289	1,543	11,833	-	-	11,833	-	-	-	-	-	-	106,469
5b.4.9	Utility Staff Cost	-	-	-	-	-	4,290	644	4,934	-	-	4,934	-	-	-	-	-	-	61,063
5b.4	Subtotal Period 5b Period-Dependent Costs	-	4,970	-	-	-	16,920	3,253	25,143	595	-	24,548	-	-	-	-	-	-	205,109
5b.0	<b>TOTAL PERIOD 5b COST</b>	-	25,312	-	-	-	20,781	6,697	52,790	823	-	51,968	-	-	-	-	-	213,520	206,829
<b>PERIOD 5 TOTALS</b>		-	25,312	-	-	-	20,781	6,697	52,790	823	-	51,968	-	-	-	-	-	213,520	206,829
<b>TOTAL COST TO DECOMMISSION</b>		6,604	94,997	15,559	21,837	44,588	875,941	183,186	1,242,712	817,219	368,347	57,145	664,829	1,002	505	357	43,958,794	1,205,190	8,079,320

<b>TOTAL COST TO DECOMMISSION WITH 17.3% CONTINGENCY:</b>	<b>1,242,712</b>	<b>thousands of 2014 dollars</b>
<b>TOTAL NRC LICENSE TERMINATION COST IS 65.8% OR:</b>	<b>817,219</b>	<b>thousands of 2014 dollars</b>
<b>SPENT FUEL MANAGEMENT COST IS 29.6% OR:</b>	<b>368,347</b>	<b>thousands of 2014 dollars</b>
<b>NON-NUCLEAR DEMOLITION COST IS 4.6% OR:</b>	<b>57,145</b>	<b>thousands of 2014 dollars</b>
<b>TOTAL LOW-LEVEL RADIOACTIVE WASTE VOLUME BURIED (EXCLUDING GTCC):</b>	<b>666,336</b>	<b>cubic feet</b>
<b>TOTAL GREATER THAN CLASS C RADWASTE VOLUME GENERATED:</b>	<b>357</b>	<b>cubic feet</b>
<b>TOTAL CRAFT LABOR REQUIREMENTS:</b>	<b>1,205,190</b>	<b>man-hours</b>

End Notes:  
n/a - indicates that this activity not charged as decommissioning expense.  
a - indicates that this activity performed by decommissioning staff.  
0 - indicates that this value is less than 0.5 but is non-zero.  
a cell containing " - " indicates a zero value